

KSCC/ADR/TEN/08/2025

27/10/2025

ദർഘാസ്

കേരളാ സ്റ്റേറ്റ് കയർ കോർപ്പറേഷൻ അടൂർ ഡിവിഷനിൽ ഫയർ ലൈനിനു ആവശ്യമായ കേബിൾ സപ്ലൈ ചെയ്യുന്നതിനും ഇടുന്നതിനും പരിചയസമ്പന്നരായ ആളുകളിൽ നിന്നും മുദ്രവച്ച കവറുകളിൽ ദർഘാസുകൾ ക്ഷണിക്കുന്നു.

പ്രവൃത്തി: അടൂർ ഡിവിഷനിലേക്ക് എലക്ട്രിക്കൽ പാനൽ റൂമിൽ നിന്നും ഫയർ പമ്പ് ഹൗസിലേക്ക് വേണ്ട കേബിൾ സപ്ലൈ ചെയ്യുന്നതിനും ഇടുന്നതിനും പമ്പ് ഹൗസിൽ പാനൽ ഫിക്സ് ചെയ്ത് കേബിൾ കണക്ഷൻ ചെയ്യുന്നതിനും മറ്റു അനുബന്ധ വർക്കുകൾക്കും പരിചയസമ്പന്നരായ ആളുകളിൽ നിന്നും മുദ്രവച്ച കവറുകളിൽ ദർഘാസുകൾ ക്ഷണിക്കുന്നു. മറ്റു വിശദ വിവരങ്ങൾ ഈ ദർഘാസിനോടൊപ്പം ഉള്ളടക്കം ചെയ്യുന്നു.

കൂടുതൽ വിവരങ്ങൾക്ക് പ്രവൃത്തി ദിവസങ്ങളിൽ അടൂർ ഓഫീസിൽ ബന്ധപ്പെടുക.
ഫോൺ - 04734 246220

ദർഘാസ് സ്വീകരിക്കുന്ന അവസാന തീയതി: സമയം: 04/11/2025; 3pm

ദർഘാസ് തുറക്കുന്ന തീയതി: സമയം: 04/11/2025; 4 pm



For and on behalf of
THE KERALA STATE COIR CORPORATION LTD.
ADOOR DIVISION

Factory Manager

എന്ന് ഫാക്ടറി മാനേജർ

പകർപ്പ് - അടൂർ ഡിവിഷൻ നോട്ടീസ് ബോർഡ്, ആലപ്പുഴ ഹെഡ് ഓഫീസ്
നോട്ടീസ് ബോർഡ്, അടൂർ കിൻഫ്രാ നോട്ടീസ് ബോർഡ്, ഏനാദിമംഗലം
പഞ്ചായത്ത് നോട്ടീസ് ബോർഡ്, കയർ കോർപ്പറേഷൻ വെബ്സൈറ്റ്

**THE KERALA STATE
COIR CORPORATION LTD.**



SCHEDULE OF WORK

1. SSB Panel fabrication, supply, installation and testing. This panel should meet the standards as per Electrical Inspectorate.
2. LT cable of 1.1 kv grade XLPE insulated supply, laying through open trench and manual excavation wherever required, testing and commissioning (3.5 C X 150 sq mm PVC Aluminium UG cable with approx 221 Metre).
3. Glanding and Termination with brass compression and aluminium lugs for XLPE insulated 1.1 kv grade cable (150 sq mm cable – 2 nos)
4. Earthing station supply (2 nos), installation, testing and commissioning comprising of earth electrode GI/copper – bonded rod/pipe), earth enhancing compound, RCC bick chamber, wires and clamps as per standards.
5. Earth Bench supply, delivery, installation testing and commissioning consisting of copper/aluminium busbars with insulators inside weather proof enclosure including all assosciated civil and other works.
6. Earthing Conductors supply with GI/copper wires for earthing of transformer, panel boards et as per technical specification. Work include all assosiated works including civil work (Approx 20 metre 25X3 GI strip.)



For and on behalf of
THE KERALA STATE COIR CORPORATION LTD.
ADOOR DIVISION

[Signature]
Factory Manager

📍 PB No. 191, Sea View Ward, Alappuzha, Kerala, India - 688001

☎ +91 477 2245044 | 2240109 | 2240101

🌐 www.coircraft.com ✉ coircorporation@coircraft.com



SMETA®



Sedex®

